


## KANSAS DRILLERS LOG

State Geological Survey  
WICHITA, BRANCHS. 31 T. 13 R. 19 <sup>E</sup>W

Loc. 1720' FWL &amp; 710' FSL NW

County Ellis

640 Acres



Locate well correctly

Elev.: Gr. 2228

DF KB 2234

API No. 15 — 051 — 21,189  
County Number

Operator

Sid Tomlinson

Address

Box 594 Twin Falls, Idaho 83301

Well No.

#2

Lease Name

RIEDEL

Footage Location

710 feet from (S) line 1720 feet from (W) line

Principal Contractor

Revlin Drlg. Inc.

Geologist

J.E. Jespersen

Spud Date

5-28-76

Total Depth

3894

P.B.T.D.

3875

Date Completed

7-14-76

Oil Purchaser

NCRA

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8 5/8	28	245'	Common	150	3% CaCl
Production	7 7/8	5 $\frac{1}{2}$	14	3893	Poz Poz	125 325	18% salt 4% gel
(stage collar at 1489'; cemented to surface)							

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jets	3838-3841
TUBING RECORD					
Size	Setting depth	Packer set at			
2 $\frac{1}{2}$	3871	none			


## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gals 15% acid	3838-3841

## INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
7-12-76	pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	36 bbls.	0 MCF	trace bbls.	0	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
			3838-3841		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator SID TOMLINSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL																
Well No. 2	Lease Name RIEDEL																	
S <u>31</u> T <u>13</u> R <u>19</u> W																		
<b>WELL LOG</b>		<b>SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.</b>																
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.																		
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME															
<p>DST #1 3846-3864 (Arbuckle)  30/30/30/30 Good blow thru-out.  Recovered 500' clean oil, 815' muddy oil, and 700' sli oil cut salt water.</p> <p style="text-align: center;">Dresser ran cased hole Gamma Ray/ Neutron log.  Electric Log Tops:</p> <table style="width: 100%; margin-top: 20px;"> <tr> <td style="width: 70%;"></td> <td style="width: 20%; text-align: right;">Anhydrite</td> <td style="width: 10%; text-align: right;">1516</td> </tr> <tr> <td></td> <td style="text-align: right;">Heebner</td> <td style="text-align: right;">3479</td> </tr> <tr> <td></td> <td style="text-align: right;">Lansing</td> <td style="text-align: right;">3522</td> </tr> <tr> <td></td> <td style="text-align: right;">Base LKC</td> <td style="text-align: right;">3760</td> </tr> <tr> <td></td> <td style="text-align: right;">Arbuckle</td> <td style="text-align: right;">3836</td> </tr> </table>					Anhydrite	1516		Heebner	3479		Lansing	3522		Base LKC	3760		Arbuckle	3836
	Anhydrite	1516																
	Heebner	3479																
	Lansing	3522																
	Base LKC	3760																
	Arbuckle	3836																
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.																		
Date Received	<div style="text-align: center;">   Signature  OPERATOR  <div style="display: flex; justify-content: center; align-items: center; margin-top: 10px;"> <div style="text-align: center; margin-right: 20px;"> 7/28/76 Date </div> <div style="text-align: center;"> Title </div> </div> </div>																	