

31-13-19w


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS CO.
Farm-G. E. Riedel No. 11

SEC. 31 T. 13 R. 19W
SW SE SW
990' fr EL, 420' fr SL of SW/4

Total Depth. 3873'
Comm. 1-22-58 Comp. 2-2-58
Shot or Treated.
Contractor. Stickle Drlg.
Issued. 5-10-58

County Ellis
KANSAS



Elevation. 2229' DF

Production. 25 BOPD

CASING:

10 3/4" 500' cem w/325 sx.
7" 3842' cem w/175 sx.

Figures indicate Bottom of Formations.

surface	35
blue shale & shells	440
shale & shells	650
sand & shale	875
shale & shells w/sand	1200
red bed & shale	1300
red bed & shells	1518
Anhydrite	1560
shale & shells	2100
lime & shale	2815
shale & lime	3225
lime & shale	3360
lime	3817
Conglomerate	3846
lime	3873
Total Depth	

TOPS:	
Heebner	3483
Toronto	3504
Lansing	3524
Base Kansas City	3769
Arbuckle	3838

Run Schlumberger Laterolog-Gamma Ray-Microlaterolog