

31. 13-19

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock Wichita, Kansas


Company - THE TEXAS CO.
Farm - Guss Riedel No. 2

SEC. 31 T. 13 R. 19W
NE SE SE

Total Depth. 3919
Comm. 3-28-51 Comp. 4-25-51
Shot or Treated.
Contractor. Anschutz Drlg. Co.
Issued. 6-23-51

County. Ellis

KANSAS



Elevation. 2287 D.F.

CASING:

10 3/4" 1571 cem w/800 sxs.
7" 3916 cem w/125 sxs.

Production. pump 109.92 BO
with trace of water in 8 hrs.

Figures Indicate Bottom of Formations.

clay	20
post rock	40
sand, shells	100
shale, shells	200
shale	690
shale, shells	950
sand, shells	1100
sand	1280
red bed	1365
red rock	1545
red rock	1560
anhydrite	1572
anhydrite	1610
shale, shells	2210
broken lime, shale	2330
lime, shale	2510
lime	2620
lime, shale	2740
broken lime	2835
lime, shale	3435
lime	3873
conglomerate	3906
conglomerate, Arbuckle	3919
Total depth	

Tops:

Cimarron Anhydrite	1562
Topeka	3281
Heebner	3535
Lansing	3577
Conglomerate	3875
Arbuckle	3887