

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


32-13-19W

Company- E. R. CAVE ET AL
Farm- Cave No. 1

SEC. 32 T. 13 R. 19W
NE NE SE

Total Depth. 3893
Comm. 12-7-51 Comp. 12-18-51
Shot or Traced.
Contractor. Strain Drlg.
Issued. 3-22-52

County Ellis
KANSAS



CASING:
8 5/8" 165' cem. w/125 sx.
5 1/2" 3881' cem. w/125 sx.

Elevation. 2261 D.F.
2262 (rod)
Production. 82 bbls. / 10% wtr.

Figures indicate Bottom of Formations.

cellar	5
post rock & shale	165
shale	1070
sand	1270
shale	1300
shale & red bed	1555
anhyd.	1595
shale & shells	2065
shale	2240
shale & lime	2300
shale & shells	2450
shale & lime	2985
shale	3170
shale & lime	3310
shale	3357
shale & lime	3465
lime	3893
Total Depth	

Tops:	
Anhyd.	1555
Heebner	3526
Lansing	3570
Base n. C.	3822
Marmaton	3852
Congl.	3866
Arb.	3879

All Meas. rotary bushings.

D.S.T. by Johnston Testing Co. 3880-3893,
open 30 min. rec. 125' of heavily oil &
gas cut mud w/some clean oil in the
middle of the fluid column. BHP 830#.