

33-13-19W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRONTIER OIL CO.
Farm- Bemis No. 1

SEC. 33 T. 13 R. 19W
NW NW SW

Total Depth. 3906'
Comm. 4-1-65 Comp. 4-9-65
Shot or Treated.
Contractor. Red Tiger Drlg. Co.
Issued. 5-29-65

County Ellis
KANSAS



Elevation. 2251' R.B.

Production. DRY

CASING:

8 5/8" 216' w/135 sx cem.

Figures Indicate Bottom of Formations.

clay rock, chalky rock	130
sdv rock, shale	217
shale	750
shale, sand strks	888
sdv lime	890
shale, shells	1547
Anhydrite	1590
shale, shells	2025
shale	2175
lime, shale	2570
lime	2585
lime, shale	3000
shale, lime shells	3080
lime	3511
shale	3514
lime	3805
Conglomerate	3903
Arbuckle	3906
Total Depth	

TOPS: SCOUT	SAMPLE
Anhydrite	1547-90
Topeka	3267
Heebner	3511
Lansing, Kansas City	3557
Marmaton chert	3839
Conglomerate	3858
Arbuckle	3903