

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company. BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Kaiser "B" No. 4

SEC. 30 T. 13 R. 20W
NW NW SE

Total Depth. 3984'
Comm. 11-26-63 Comp. 12-5-63
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg.
Issued. 3-7-64

County Ellis

KANSAS



Elevation. 2310' DF

Production. Dry

CASING:
8 5/8" 205" cem w/160 sx.
5 1/2" 3977' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay	30
shale & shells	1100
sand	1340
shale	1395
shale & shells	1510
redbed & shale	1633
Anhydrite	1682
shale & shells	2205
shale & lime	3433
lime	3565
shale & lime	3623
lime	3753
lime & shale	3895
lime	3902
chert	3940
chert & shale	3958
lime	3970
lime & chert	3980
lime	3982 RTD
lime ?	3984
Total Depth	

TOPS: LOG

Anhydrite	1633
Heebner	3563
Toronto	3582
Lansing	3601
Marmaton	3902
Arbuckle	3978

DST #1 3946-70' Op 30" Rec. 15' mud, BHP 536#, 203# (F51#-66#).

DST #2 3946-82' Op 1 hr. 35". Rec. 140' mud w/speaks oil. BHP 1102#/548#.