

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

6-13-20

COMPANY KAISER-FRANCIS

FARM Bittel "A"

NO. 3

SEC. 6 T. 13 R. 20W
LOC. NE NW SE

TOTAL DEPTH 3828'

COMM. 5-22-67

COMP. 5-29-67

SHOT OR TREATED

CONTRACTOR Rains & Williamson Oil Co., Inc.

ISSUED 8-5-67

COUNTY Ellis

KANSAS

CASING

20	10	
15	8 5/8	236' w/150 sx cem.
12	6	
13	5 1/2	3819' w/120 sx cem.

ELEVATION 2163' KB

PRODUCTION 35 BOPD/NW
ARB 3819-34

FIGURES INDICATE BOTTOM OF FORMATIONS

Soil, sand, clay	90'
Shale	242'
Shale and shells	995'
Sand	1210'
Shale	1495'
Anhydrite	1547'
Shale	2102'
Lime and shale	2315'
Lime	2600'
Shale and lime	2865'
Shale	3245'
Lime w/shale	3460'
Lime	3778'
Lime w/chert	3800'
Lime	3828'
Rotary Total Depth	3828'

Set 5-1/2" prod. csg.
at 3819. First stage
cemented w/120 sx.
common; second stage
cemented w/350 sacks
50-50 Pozmix, 6% gel.

TOPS: SCOUT	SAMPLE
Anhydrite	1495
B/Anhydrite	1547
Topeka	3185
Heebner	3417
Toronto	3440
Lansing	3456
B/Kansas City	3696
Marmaton	3752
Conglomerate	3797
Arbuckle	3818

We certify the above log is
true and correct to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the
County of Sedgwick, State of Kansas, this 2nd day of June, 1967.

Mary J. Brown
Mary J. Brown Notary Public

My Commission Expires:
March 3, 1970

Oil & Gas Records Division
State Geological Survey of Kansas