

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

6-13-20W

COMPANY RAINS & WILLIAMSON OIL

SEC. 6 T. 13 R. 20W
LOC. SE SW NE

FARM Clon Dittel

NO. 3

TOTAL DEPTH 3840

COMM. 4-11-67

COMP. 4-19-67


SHOT OR TREATED

CONTRACTOR Rains & Williamson

ISSUED 6-10-67

COUNTY Ellis

KANSAS



CASING

20	10	
15	8 5/8"	@ 212' w/150 SX
12	6	
10	5 1/2"	@ 3837' w/100 SX

ELEVATION 2168' KB

PRODUCTION PMP 90 DOPD, 177
ARB 3837-40

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	214'
Shale and Shells	640'
Shale	997'
Sand	1214'
Shale	1497'
Anhydrite	1551'
Shale	2100'
Lime and Shale	2690'
Shale and Lime	3055'
Lime and Shale	3360'
Lime	3770'
Lime and Chert	3830'
Lime	3840'

TOPS: SCOUT

Anhydrite	1497
B/ "	1551
Topeka	3192
Heebner	3425
Toronto	3443
Lansing	3462
B/Kansas City	3709
Marmaton	3762
Conglomerate	3812
Arbuckle	3836

non cement, salt
flush ahead.

Pottery Total Depth 3840'

We certify the above log is
true and correct to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of
Kansas, County of Sedgwick, this 24th day of April, 1967.

Mary J. Brown, Notary Public