

Operator ICER ADDIS DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name KOHL DRY HOLE

S 7 T 13 R 20 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1,527			
Topeka	3,209			
Heebner	3,442			
Toronto	3,461			
Lansing	3,478			
Base Kansas City	3,725			
Marmaton Chert	3,806			
Conglomerate	3,840			
Conglomerate sand	3,862			
Arbuckle	NONE			
Rotary Total Depth	3,908			
DST #1: Open 60" (30-30-30-30) Recovered 30' muddy salt water; ISIP 970#, FSIP 908#, IFP 11-21#, FFP 21-42#.	3,645	3,675		
DST #2: Open 60" (30-30-30-30) Fair blow. Recovered 60' oil cut mud, 90' dark gray heavy oil cut mud. ISIP 1107#, FSIP #1033#, IFP 42-64#, FFP 106-138#.	3,818	3,870		
Plugged and Abandoned at RTD	3,908			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD

Date Received

Icer Addis
Icer Addis Signature
Owner-Operator Title
December 15, 1977 Date