

12-13-20W

WILLIAMSON DRILLING, INC.

5501 NAVAJO

GREAT BEND, KANSAS 67530

(316) 793-8229

DRILLERS' WELL LOG

DATE COMMENCED: July 31, 1986
DATE COMPLETED: August 7, 1986

DaMar Resources, Inc.
Krause #1
150' W of NE NE SW
Sec. 12, T13S, R20W
Ellis County, Ks.

Surface Pipe: Ran 6 Jts. New 20# 8 5/8"
casing. Set @ 258'. Cemented w/140 sks.
50/50 Poz, 2% Gel, 3% CC.

Elevation: 2080' G.L.
2085' K.B.

0 - 1100' Surface Soil, Post Rock, Sand
& Clay
1100 - 1420' Redbed
1420 - 1458' Anhydrite
1458 - 3050' Shale w/Lime Stringers
3050 - 3106' Shale
3106 - 3355' Lime w/Shale Stringers
3355 - 3360' Carb. Shale
3360 - 3723' Lime w/Shale Stringers
3723 - 3756' Conglomerate
3756 - 3791' Dolomite
3791' R.T.D.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss.

Terry L. Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.