


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRLG. CO.
Farm- Anderson No. 1

SEC. 13 T. 13 R. 20W
SE NE SW

Total Depth. 3990'
Comm. 1-23-59 Comp.2-3-59
Shot or Treated.
Contractor.
Issued. 7-4-59

County Ellis
KANSAS



Elevation. 2219' DF

Production. 79 BOPD

CASING:

8 5/8" 191' cem w/140 sx.
5 1/2" 3967' cem w/200 sx.

Figures indicate Bottom of Formations.

clay, sand & shale	100
shale	490
sand & shale	590
shale	700
shale & sand	1050
sand	1265
shale & strks sand	1325
red bed	1557
Anhydrite	1604
shale & shells	2100
brown line	2175
line & shale	2630
shale & shells	2725
line & shale	3055
shale & line strks	3111
line & shale	3275
line	3562
line & chert	3564
line	3850
line & chert	3905
Conglomerate	3943
Arbuckle line	3990 RTD
Total Depth	

#4 3650-67', op 15 min. wk. blow 10 min.,
rec. 15' mud, FSIP 400# going up.

#5 3704-15', op 30 min., rec. 45' mdt. wtr.
ISIP 1380#, FSIP 1360#.

#6 3829-50', op 20 min, wk. blow 10 min.,
rec. 15' mud. FSIP 760#.

TOPS:

Anhydrite	1556
Heebner	3484
Toronto	3506
Lansing	3521
Marnaton	3831
Arbuckle	3927

DRILL STEM TESTS:

#1 3278-92', op 1 hr., had a weak blow
thruout, rec. 40' wtry mud, ISIP 970#
FSIP 950#.

#2 3547-64, op 30 min., rec. 2365' gas,
340' oil & wtr. cut mud, 700' clean oil
300' clear wtr. ISIP 1060#, FSIP 1020#.

#3 3572-84', op 45 min, weak blow 45 min.,
rec. 63' ndy wtr, ISIP 1120#, FSIP 1040#.