

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- BIRMINGHAM-BARTLETT DRLG. CO.
 Farm- Herbert No. 2

SEC. 18 T. 13 R. 20W
 NE SE SW

Total Depth. 3882'
 Comm. 12-6-58 Comp. 12-17-58
 Shot or Treated.
 Contractor.
 Issued. 3-7-59

County Ellis

KANSAS



Elevation. 2227' RB

Production. 149 BOPD

CASING:

8 5/8" 208' cem w/150 sx.
 5 1/2" 3878' cem w/200 sx.

Figures indicate Bottom of Formations.

shale	950
shale & sand	1285
shale & red bed	1560
Anhydrite	1612
shale & shells	2125
shale & lime	2195
lime	2230
lime & shale	2640
shale & lime shells	2740
lime & shale	2837
shale & lime streaks	2910
lime & shale	3000
shale & lime streaks	3107
lime	3130
lime & shale	3250
lime	3313
lime & shale	3382
lime	3835
lime & chert	3881 RTD
lime	3882 CTD
Total Depth	

TOPS:

Anhydrite	1560
Heebner	3473
Toronto	3495
Lansing	3510
Marmaton Chert	3814
Arbuckle	3876

DST #1 3504-25', op 1 hr., rec. 2850'
 gas, 376' oil, ISIP 1170#, IFP 0#, FFP 147#,
 FSIP 1105#.

DST #2 3728-36', op 30 min. rec. 17'
 mud. SIP 0.

DST #3 3822-38, op 8". no blow, flushed
 tool, rec. 20' mud. ISIP 0#, FSIP 1060#,
 (?).

Tested 2 BOPH natural, acidized w/500
 gal.