

508 East Murdock,

Wichita, Kansas

18-13-20W

Company- BIRMINGHAM-BARTLETT DRLG. CO.
 Farm- Stebbins "A" No. 1

SEC. 18 T. 13 R. 20W
 SW NW SE

Total Depth. 3395'

Comm. 4-15-59

Comp. 4-25-59


Shot or Treated.

Contractor.

Issued. 7-18-59

County Ellis

KANSAS



Elevation. 2203' DF

Production. Dry

CASING:

8 5/8" 199' cem w/150 sx.

Figures Indicate Bottom of Formations.

clay - rock	25
sand	35
shale	515
sand	590
shale	890
H. sand & shale	950
shale & sand	1060
sand	1260
red bed	1542
Anhydrite	1590
shale & shells	2090
broken lime	2235
lime & shale	2615
shale & lime strks	2745
lime & shale	3330
lime	3792
lime & chert	3842
shale & chert	3862
lime & chert	3895
Total Depth	

TOPS:

Anhydrite	1542
Heebner	3466
Toronto	3487
Lansing	3505
Marmaton Chert	3799
Arbuckle	3881

DST #1 3497-3515', op 1 hr, had wk. blow
 for 7 min., rec. 11' mud, all pressures 0#.

DST #2 3530-3543', op 1 hr, fair blow,
 rec. 135' wtr., BHP 360#.

DST #3 3626-3720', op 1 hr., rec. 480'
 wtr, 1300# BHP.

DST #4 3806-3842', op 1 hr, rec. 210'
 very slightly oil cut mud, 40' wtr,
 BHP 965#.

DST #5 3881-3885', op 1 hr, no blow,
 rec. 5' mud, BHP 560#.