

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


20-13-20W

Company- BIRMINGHAM-BARTLETT DRLG. CO.
Farm- Flax No. 2

SEC. 20 T. 13 R. 20W
SW NW SW

Total Depth. 3906'
Comm. 5-19-61 Comp. 5-28-61
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg.
Issued. 9-16-61

County Ellis
KANSAS



CASING:

8 5/8" 183' cem w/150 sx.
5 1/2" 3893.5' cem w/200 sx.

Elevation. 2255' DF

Production. 108 BOPD

Figures Indicate Bottom of Formations.

surface clay	30
sand shale	184
shale	500
shale & shells	1090
sand	1275
shale & red bed	1565
red bed	1576
Anhydrite	1622
shale & shells	1945
shale	2205
lime & shale	2680
shale	2715
shale & lime	3440
lime	3563
shale & lime	3625
lime	3690
shale & lime	3715
lime	3847
chert	3876
shale & lime	3892
Arbuckle	3895 RTD
Arbuckle	3906 CTTD
Total Depth	

TOPS:

Anhydrite	1576
Heebner	3503
Toronto	3523
Lansing	3540
Marmaton	3832
Arbuckle	3892

DST #1 3602-33', op 50 min, rec. 360'
oil & 1800' wtr, BPH 1100#/1075#.

DST #2 3669-3715', op 20 min, rec. 10'
mud. All pressures 0#.

DST #3 3722-55', op 1 hr, rec. 60' mud,
BHP 740#-60#.

DST #4 3762-90', op 15 min, rec. 5' mud,
BHP none.