

DRILLER'S LOG

COMPANY: C & C Exploration

SEC. 21 T. 13S R. 20W

LOC. SE/4

WELL NAME: HERBERT #1

COUNTY: Ellsworth

RIG NO. 9

TOTAL DEPTH 3900'

ELEVATION

COMMENCED: 8-7-85

COMPLETED: 8-14-85

CONTRACTOR: RAINS & WILLIAMSON OIL CO., INC.

CASING RECORD:

SURFACE: 8 5/8" @ 214' w/ 150 sx. 60/40 poz., 3% cc., 2% gel.

PRODUCTION: 4 1/2" @ 3899' 1/ 160 sx. 60/40 poz., 10% salt., 2% gel., 1/4 floreal

LOG

(Figures Indicate Bottom of Formations)

SEP 16 1985
State Geological Survey
MANKY

Clay	217
Sand and Shale	981
Shale	1546
Anhydrite	1590
Shale	1922
Shale and Sand	2320
Shale	2845
Shale and Lime	3240
Lime and Shale	3257
Shale and Lime	3261
Lime and Shale	3588
Lime	3793
Lime and Shale	3815
Lime	3840
Lime and Shale	3900
<u>Rotary Total Depth</u>	<u>3900</u>

STATE OF KANSAS)

COUNTY OF SEDGWICK)

SS: