


22 - 13 - 20 W^N

KANSAS DRILLERS Log *State Geological Survey*
 WICHITA, BRANCH
 API No. 15 — 051 — ~~20,061~~ 21,061
 County Number
 Operator Icer Addis
 Address Box 8038, Wichita, Kansas 67208
 Well No. #1 Lease Name Honas
 Footage Location
 feet from (N) (S) line feet from (E) (W) line
 Principal Contractor DUKE DRILLING COMPANY Geologist Richard M. Foley
 Spud Date May 16, 1975 Total Depth 3,910' P.B.T.D.
 Date Completed May 23, 1975 Oil Purchaser

S. 22 T. 13 R. 20 W^E
 Loc. NE NW NW
 County Ellis



Elev.: Gr. 2,201'
 DF 2,203 KB 2,206

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28#	243	Common	150	3% Gel, 2% Ca Ch

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production **Dry Hole** Producing method (flowing, pumping, gas lift, etc.)
 RATE OF PRODUCTION PER 24 HOURS
 Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
 Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

State Geological Survey
WICHITA, BRANCH

DRILLERS' WELL LOG

15-051-21061
22-13-20W

DATE COMMENCED: May 16, 1975
DATE COMPLETED: May 24, 1975

Icer Addis
HONAS # 1
NE NW NW of Sec. 22-T13S-R20W
Ellis County, Kansas

ELEVATION: 2206 K.B.

0 - 955'	Shale, Post Rock, Sand Streaks
955 - 1040'	Sand, Shale
1040 - 1257'	Sand
1257 - 1551'	Red Bed
1551 - 1590'	Anhydrite
1590 - 2120'	Shale and Shells
2120 - 2815'	Lime, and Shale
2815 - 2985'	Shale
2985 - 3300'	Shale and Lime
3300 - 3454'	Lime
3454 - 3458'	Shale
3458 - 3752'	Lime
3752 - 3823'	Lime and Shale
3823 - 3852'	Shale, Lime, Chert and Sand
3852 - 3870'	Sand
3870 - 3910'	Dolomite
3910'	RTD

FORMATION TOPS

Anhydrite	1551
Topeka	3223
Heebner	3454
Lansing	3492
Base K.C.	3752
Cong.	3823
Cong. Sand	3852
Artuckle	3870
RTD	3910



SURFACE PIPE:
Set 243' of 8 5/8", 28# used
pipe w/150 sacks Common, 2% Gel,
3% cc. RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1975

A F F I D A V I T

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 27th day of May, 1975.

Harathy M. Hague
Notary Public

My Commission Expires: April 11, 1978