


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO. ET AL
Farm- Younger No. 5

SEC. 25 T. 13 R. 20W
SE SE SE

Total Depth. 3833'
Comm. 9-26-57 Comp. 10-13-57
Shot or Treated.
Contractor. Sterling Drlg. Co.
Issued. 1-4-58

County Ellis
KANSAS



Elevation. 2209 RB

Production. 193 BOPD

CASING:

8 5/8" 240' w/150 sx cem.
5 1/2" 3829' w/150 sx cem.

Figures indicate Bottom of Formations.

clay-sand	70
shale-shells	241
shale-sand	1000
sand	1175
shale-red bed	1490
Anhydrite	1525
shale-shells	1780
shale-lime	2180
lime	2350
shale-lime	3075
lime	3405
lime-shale	3470
lime	3705
lime-conglomerate	3765
lime-chert	3820
lime	3833
Total Depth	

TOPS: RB

Topeka	3194
Heebner	3448
Toronto	3468
Lansing	3492
B/Kansas City	3736
Marmaton cherty	
Limestone	3774
Conglomerate	3792
Arbuckle	3827

10-12-57 - Acidized w/250 gals.
10-13-57 - " w/500 "
10-13-57 - " w/1000 "