

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company. IMPERIAL DRILLING CO., INC.
Farm Giebler No. 3

SEC. 27 T. 13 R. 20W
SW NE SW

Total Depth. 3935
Comm. 5-25-53 Comp. 6-22-53
Shot or Treated.
Contractor. Imperial Drilling Co., Inc.
Issued. 8-8-53

County Ellis

KANSAS



CASING:

8 5/8 195' w/ 150 sx cement
5 1/2 set at 3935' w/ 200 sx cement

Elevation. 2244 RB

Production. 625 BOPD

Figures indicate Bottom of Formations.

surface clay & sand	70
shale & shells	97
surface sand & clay	195
shale & shells	965
Dakota sand	1210
red bed, shale & shells	1420
shale & shells	1548
anhydrite	1592
shale & shells	2135
lime & shale	3410
lime	3794
lime & chert	3831
shale	3833
conglomerate	3837
Arbuckle	3935
Total Depth	

TOPS:

Anhydrite	1548
Heebner	3467
Lansing	3506
Base KC	3762
Marmaton chert	3805
Conglomerate	3833
Arbuckle	3837

DST #1: 3682-99, open 45 min. strong
blow, rec. 240' HGCMdyO, 200' free
oil. 1060' gas in pipe above oil
BHP 1225# 15 min.

DST #2: 3844-71, open 1 hr. strong
blow, Rec. 1600' free oil, 600' gas
in pipe above oil, BHP 990#, FFP 555#
IFP 120# 15 min.

DST #3: 3874-92, open 1 hr. strong
blow, rec. 2400' SW, 1t. tr. oil
BHP 1065#, FFP 1050#, IFP 300# 15 min.

Core #1 3828-42
Core #2 3842-3892
Core #3 3892-3927