

WICHITA BRANCH
WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 051 — 21,821 ✓
County NumberS. 27 T. 13 R. 20 R
W

Loc. NW SE SE

County Ellis

Operator

John B. Collins

Address

1007 Cody, Suite A Hays, Kansas 67601

Well No. #4

Lease Name
Giebler

Footage Location

990 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor

Dreiling Oil, Inc.

Geologist

Lawrence F. Gray

Spud Date

10-26-79

Date Completed

11-1-79


Total Depth

3830

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

640 Acres
N

Locate well correctly

Elev.: Gr. 2194

DF 2196 KB 2199

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Pipe	12 1/4	8 5/8		188	common	130	7 units quickset
Production	7 7/8	5 1/2		3820	common	125	8% salt 4% gilsonite .1 of 1% GDL

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator John B. Collins		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: oil
Well No. 4	Lease Name Giebler	
S 27 T 13 R 20 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Top Soil	0	65		
Shale	65	745		
Shale & Sand Streaks	745	978		
Sand	978	1207		
Shale & Red Bed	1207	1228		
Red Bed	1228	1502		
Anhydrite	1502	1543		
Shale	1543	2085		
Lime & Shale	2085	2335		
Shale & Lime	2335	2780		
Shale	2780	3070		
Lime & Shale	3070	3250		
Lime	3250	3324		
Shale & Lime	3324	3597		
Lime	3597	3830		
	3830	T.D.		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature <i>John B. Collins</i>
	Title <i>Operator</i>
	Date <i>1-11-80</i>

Ind

61

Company

Farm

Total Depth

Comm.

Contractor

Cement Record

130 sacks cement
cemented w/125 sacks
common

Production:

State Geological Survey
WICHITA BRANCH

Figures Indicate Bottom of Formations

Top Soil
Shale
Shale & Sand streaks
Sand
Shale & Red Bed
Red Bed
Anhydrite
Shale
Lime & Shale
Shale & Lime
Shale
Lime & Shale
Lime
Shale & Lime
Lime

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Giebler #1.


Joseph A. Hess

Subscribed and sworn to before me this 8th day of November, 1979.

Cecilia Basgall
Cecilia Basgall Notary Public