


Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Giebler "C" No. 2

SEC. 27 T. 13 R. 20W
 SW SW NE

Total Depth. 3942'
 Comm. 12-17-57 Comp. 1-14-58
 Shot or Treated.
 Contractor. Imperial Oil of Kans., Inc.
 Issued. 5-10-58

County Ellis
 KANSAS



Elevation. 2206' KB

Production. 28 BOPD, 54% Wtr.

CASING:

8 5/8" 216' cem w/175 sx.
 5 1/2" 3875'

Figures indicate Bottom of Formations.

sand, shale & shells	216
shale & shells	625
shale, shells & sand	1250
shale & shells	1512
Anhydrite	1556
shale & shells	2085
shale & lime	3450
lime	3535
shale & lime	3573
lime	3834
Arbuckle	3942 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Anhydrite	1512	1512
Topeka	3199	3199
Heebner	3446	3445
Toronto	3467	3467
Lansing	3485	3485
Base Kansas City	3732	3732
Cherty Conglomerate	3778	3778
Conglomerate Sand	3820	3820
Arbuckle	3826	3826

DRILL STEM TESTS:

- #1 3663-71, open 1 hr., rec. 10' salt water cut mud, BHP 30#.
- #2 3680-3727, open 2 hrs., rec. 840' gas, 120' slightly oil cut mud, 120' heavily oil & gas cut mud, BHP 820#.
- #3 3680-3706 (Straddle Test) Strong blow for 20 min. lost top packer seat, reset packer, open 1 hr., rec. 720' gas, 120' slightly oil & gas cut mud, 665' drilling mud, BHP 520# (?)
- #4 3827-34, open 3 hrs., rec. 75' heavily oil cut mud, 75' clean oil. BHP 1060#.
- #5 3834-43, open 2 hrs., rec. 90' heavily oil cut mud, 170' clean oil. BHP 850#.
- #6 3843-54. open 2 hrs. rec. 2' oil. 690' salt water.