


Company- IMPERIAL OIL OF KANSAS, INC.  
 Farm- Waldschmidt No. 3

SEC. 27 T. 13 R. 20W  
 SW NE NW

Total Depth. 3830'  
 Comm. 6-29-57 Comp. 7-22-57  
 Shot or Treated.  
 Contractor. Imperial Oil of Kansas, Inc.  
 Issued. 11-9-57

County Ellis KANSAS



Elevation. 2210' RB

Production. 265 BOPD

## CASING:

8 5/8" 230' cem. w/175 sx  
 5 1/2" 3827' cem.

Figures indicate Bottom of Formations.

shale, shells & sand	1520
anhydrite	1558
shale & shells	2295
shale & lime	3435
lime	3800
lime (Cherty)	3830 RTD
Total Depth	

D.S.T. #9. 3704-32 Open 2 hrs. Rec.  
 810' gas, 65' oil cut mud, 30' mud cut  
 oil & 30' clean oil. BHP 360#.

TOPS:	
Anhydrite (scout)	1520
Topeka	3144
Heebner	3438
Toronto	3460
Lansing-Kansas City	3478
Base Kansas City	3733

D.S.T. #1. 3472-81 Open 2 hrs. Rec.  
 75' saltwater. BHP 75#.

D.S.T. #2. 3554-63 Open 2 hrs. Rec.  
 130' salt water with a scum of oil.  
 BHP 1190#.

D.S.T. #3. 3567-72 Open 2 hrs. Rec.  
 1035' gas, 60' heavily oil cut mud,  
 90' mud cut oil & 150' salt water.  
 BHP 1005#.

D.S.T. #4. Open 1 hr. Rec. 30' slightly  
 water cut mud. BHP 615#

D.S.T. #5. 3583-95 Open 2 hrs. Rec.  
 225' saltwater. BHP 1135#

D.S.T. #6. 3628-40 Open 1 hr. Rec.  
 15' mud. BHP 35#.

D.S.T. #7. 3652-62 Open 2 hrs. Rec.  
 280' salt water with slight show of  
 oil. BHP 1155#.

D.S.T. #8. 3677-85 Open 2 hrs. Rec.  
 925' gas, 60' mud cut oil and 35' clean  
 oil. BHP 1135#.