


KANSAS DRILLERS LOG

API No. 15 — 051 — 21,546
County Number

S. 29 T. 13 R. 20 ■ W

Loc. SE SW NE

County ELLIS

640 Acres
N

Locate well correctly

Elev.: Gr. 2308'

DF KB 2313'

Operator

ICER ADDIS

Address

Drawer 8038, Wichita, Kansas 67208

Well No.

#1

Lease Name

FLAX

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

DUKE DRILLING CO., INC.

Geologist

Richard M. Foley

Spud Date

August 19, 1978

Total Depth

3,960

P.B.T.D.

Date Completed

August 27, 1978

Oil Purchaser

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"		207'	50-50 Pozmix	140	
Production		4-1/2"	10.5#	3,955'	60-40 Pozmix	125	6% gel

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	3961'	None

None, open hole completion

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Deepened to 3961', clean out and acidize w/250 Gal. NE 15%	
by Service Acid	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
9-13-78	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	25 bbls.		25 bbls.		
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
			Arbuckle		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ICER ADDIS		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name FLAX		OIL WELL
S <u>29</u> T <u>13</u> R <u>20</u> ^D _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Anhydrite	1,629		
Topeka	3,326		
Heebner	3,563		
Toronto	3,585		
Lansing	3,603		
Base Kansas City	3,852		
Marmaton	3,894		
Arbuckle	3,944		
Rotary Total Depth	3,960		
DST #1: Open 45" (30-30-15-30) Recovered 20' mud. ISIP 1107#, FSIP 1096#, IFP 43-43#, FFP 53-53#.	3,470	3,521	
DST #2: Open 60" (30-30-30-30) Recovered 350' muddy water. ISIP 824#, FSIP 824#, IFP 32-106#, FFP 128-191#.	3,680	3,700	
DST #3: Open 60" (30-30-30-30) Increasing to strong blow. Recovered 300' clean oil, 120' very muddy oil. ISIP 1149#, FSIP 1117#, IFP 32-74#, FFP 96-138#	3,950	3,960	
Completion in Arbuckle (No other zones recommended for completion)			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<div style="text-align: right;"> Icer Addis Signature Owner-Operator Title 9-19-78 Date </div>		