

Company- BIRMINGHAM-BARTLETT DRIG.
Farm- Kaiser "B" No. 1

SEC. 30 T. 13 R. 20W
NW SW SE

Total Depth. 3926'

Comm. 3-30-59

Comp. 4-10-59


County Ellis

KANSAS

Shot or Treated.

Contractor.

Issued. 7-4-59



CASING:

8 5/8" 209' cen w/150 sx.

5 1/2" 3921' cen w/200 sx.

Elevation. 2283' DF

Production. 70 BOPD

Figures Indicate Bottom of Formations.

shale & shells	203
shale	340
shale & sand	375
shale & shells	515
shale, iron & sand	1110
sand	1340
red bed	1609
Anhydrite	1666
shale & shells	2190
shale & lime	3085
shale	3115
lime & shale	3320
lime	3655
lime & shale	3710
lime	3905
Conglomerate	3919
Arbuckle	3923 RTD
lime	3926 CTTD
Total Depth	

#6 3715-30', op 1 hr., gas to surf. in
20 min., rec. 2160' oil, ISIP 1400#,
FSIP 1100#.

#7 3750-60', op 1 hr., rec. 2340' gas,
360' oil, ISIP 1380#, FSIP 1000#.

#8 3764-75', op 15 min, rec. 10' mud,
w/specks oil, all pressures 0#.

TOPS:

Anhydrite	1609
Heebner	3526
Toronto	3547
Lansing	3565
Marmaton	3871
Conglomerate	3905
Arbuckle	3919

DRILL STEM TESTS:

#1 3556-70', op 1 hr, had gas to surf.
in 50 min., rec. 630' gassy oil, ISIP
1275#, FSIP 1165#.

#2 3583-3604', op 1 hr., gas to surf.
in 1 hr., rec. 1060' gassy oil, ISIP 1125#,
FSIP 995#.

#3 3603-20', op 15 min., rec. 15' mud,
all pressures 0#.

#4 3620-42', op 1 hr., had gas to surf.
in 1 hr., rec. 780' oil, ISIP 1260#,
FSIP 1160#.