

DRILLERS LOG

Geological Survey
 WICHITA BRANCH
 JUN 8 0 RECD
 30-13-20W
 SE NE NE

OPERATOR: Green Oil Operations Box 503 Hays Kansas 67601

CONTRACTOR: **White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042**

Lease Name Flax #3 Well No. _____

Sec. 30 T. 13 R. 20w Spot SE NE NE

County Ellis State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 259' with 200, 2% gel. Sxs.
3% cc.

Production: _____ @ _____ with _____ Sxs.

Type Well: Oil Total Depth 3975'

Drilling Commenced: 5/2/80 Drilling Completed 5/13/80

Formation	From	To	Tops
Cellar	0	5	Kansas City - 3614
Lime, Surface	5	45	
Shale, Sandy	45	100	
Lime	100	260	
Shale, Lime	260	1100	
Sand	1100	1376	
Shale, Lime	1376	1709	
Shale, Lime (Strks)	1709	2160	
Shale, Lime	2160	3060	
Shale, Lime (Strks)	3060	3190	
Lime	3190	3377	
Lime, Shale	3377	3409	
Lime, Shale (Strk)	3409	3476	
Lime	3476	3531	
Lime, Shale	3531	3614	
Lime (K.C.)	3614	3975	

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots
-----------	---------------------	--------------