


REC'D MAR 20 1974

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 051 — 20,947
County NumberS. 32 T. 13 R. 20 ²W

Loc. 200' W NE SW SE

County Ellis

640 Acres
N

Locate well correctly

Elev.: Gr. 2280

DF 2283 KB 2285

Operator

G. N. Rupe

Address 925 O. W. Garvey Bldg., 200 West Douglas Wichita, Ks.

Well No.

#2

Lease Name

Boos

Footage Location

755 feet from (S) line

1769 feet from (E) line

Principal Contractor

Red Tiger Drly.

Geologist

W. B. Clement

Spud Date

March 28, 1974

Total Depth

3919

P.B.T.D.

Date Completed

May 1, 1974

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12"	8 5/8		208	Common	160	2% Gel 3% CaCl
Production	9 5/8	5 1/2	15 1/2	3917	50-50 Pozmix 1st stop	125	Salt Sat.
					2nd stop	300	6% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			None		

TUBING RECORD

Size	Setting depth	Packer set at
2 7/8	3165	3158

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production <i>May 6, 1974</i>		Producing method (flowing, pumping, gas lift, etc.) <i>Pump</i>			
RATE OF PRODUCTION PER 24 HOURS	Oil <i>300</i> bbls.	Gas MCF	Water <i>None</i> bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) <i>3917-19 open hole</i>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator G. N. RUPE		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL
Well No. 2	Lease Name B 0 0 5	
S <u>32</u> T <u>135</u> R <u>20</u> ^W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<i>Anky dritr</i>	1594	1638		
<i>Heebner</i>	3528	3532		
<i>Landing</i>	3562	3813		
<u>DST #1</u> 3555-3610 30-30-30-30 Rec. 157' 93 g.c. mud, ISIP 195 # IFP 31-62 FFP 62-93 # FSIP 187, T-116°				
<i>Reagan</i>	3916	?		
<i>RTD</i>	3919			
<u>DST #2</u> 3715-3766 30-30-45-30 Rec. 100' oil speckled mud ISIP 140 # IFP 39-62 FFP 62-78 # FSIP 129, T-117°				
<u>DST #3</u> 3897-3919 30-30-30-30 Rec. 2700' gassy free oil, 140' muddy oil, ISIP 1157 FFA 797 # FFP 1000 # FSIP 1157, T-130°.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

	G. N. RUPE	
	By: <u>W. G. Clement</u>	
	Signature	
	<u>Petroleum Geologist</u>	
		Title
		<u>Sept. 19, 1974</u>
		Date