


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
**508 East Murdock, Wichita, Kansas**

Company- THE TEXAS CO.  
 Farm- W.A. Nicholson No. 2

SEC. 34 T. 13 R. 20W  
 SE NE NW

Total Depth. 3972'  
 Comm. 1-27-54 Comp. 3-8-54  
 Shot or Treated.  
 Contractor. Stickle Drilling Co.  
 Issued. 7-24-54

County Ellis  
 KANSAS



**CASING:**

10 3/4" 276' cem w/200 sx  
 7" 3890' cem w/200 sx

Elevation. 2217' DE

Production. SWD

Figures indicate Bottom of Formations.

post rock & clay	40
shale	278
shale & shells	1000
shale & sand	1275
shale & shells	1515
anhydrite	1565
shale & shells	1785
shale & lime	2125
lime & shale	2275
shale & lime	2435
lime	<b>2540</b>
shale & lime	2850
lime	3816
lime & sand	3830
lime	3844
sand & dolomite	3879
lime	3907
sand	3924
shale & lime	3949
sand & lime	3963
granite	3972
Total Depth	

<b>Tops:</b>	
Cimaron Dolomite	1521
Topeka	3198
Heebner	3446
Toronto	3468
Lansing	3485
Marmaton	3778
Conglomerate	3805
Arbuckle	3874
Granit Wash	3930
Granit	3948