


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - B & R DRLG. CO.  
Farm - Kingsley No. 1.

SEC. 34 T. 13 R. 20 W  
SE NE SE

Total Depth. 3844'  
Comm. 6-12-45 Comp. 7-9-45  
Shot or Treated.  
Contractor.  
Issued. 10-27-45

County. Ellis  
KANSAS



CASING:  
8 5/8" 198' Cem.  
5 1/2" 3831' Cem.

Elevation. 2232.06

Production. Pot. 220 B0  
plus 25 BW

Figures Indicate Bottom of Formations.

|                               |       |
|-------------------------------|-------|
| shale                         | 60    |
| sand                          | 75    |
| shale & Shell                 | 200   |
| shale & lime shells           | 565   |
| shale & shells.               | 710   |
| sandy                         | 760   |
| shale & shells                | 900   |
| sand & shale                  | 960   |
| shale & sand strks.           | 1050  |
| sand red                      | 1200  |
| shale                         | 1305  |
| pyrite of iron &<br>red shale | 1474  |
| red shale                     | 1505  |
| shale                         | 1525  |
| anhydrite                     | 1565  |
| shale                         | 1630  |
| shale & shells                | 1960  |
| salt                          | 2080  |
| anhydrite & shale             | 2140  |
| lime & shale                  | 2205  |
| lime                          | 2265  |
| sandy lime & shale            | 2335  |
| lime                          | 2485? |
| lime & shale                  | 2565  |
| lime                          | 2600  |
| lime & shale                  | 2689  |
| shale red                     | 2710  |
| lime & shale                  | 3168  |
| lime                          | 3178? |
| lime & shale                  | 3220  |
| lime                          | 3307  |
| lime & shale                  | 3342  |
| lime                          | 3415  |
| lime & shale                  | 3453  |
| lime                          | 3833  |
| lime Arbuckle                 | 3844  |
| Total Depth                   |       |