

508 East Murdock  
Wichita, Kansas

AUG 15 1970

*Storms*

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

34-13-20W  
NE NW NE

Elm. 2217' KB

P. 3080+40BW  
ark.

**STORMS #1**

NE NW NE Section 34-13S-20W  
Ellis County, Kansas

Commenced: April 21, 1970  
Completed: April 29, 1970

OPERATOR - Ottawa Petroleum & Exploration Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	80	Post rock	
60	241	Shale and shells	Ran 6 joints 8-5/8" casing, set @ 239' w/185 sacks cement.
241	741	Shale	
741	1000	Shale and shells	
1000	1200	Sand	
1200	1521	Shale	
1521	1560	Anhydrite	
1560	1930	Shale and shells	
1930	3387	Shale and lime	
3387	3843	Lime	
3843	TD		Ran 121 joints 5-1/2" casing, set @ 3829' w/200 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NE NW NE Section 34-13S-20W, Ellis County, Kansas, to the best of my knowledge and belief.



*E. E. Hall*  
E. E. HALL

STATE OF KANSAS )  
) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 4 day of May, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument.

Storms No. 1

34-13-20W  
NE NW NE