


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D.G. HANSEN
 Farm- John Strom
 (Storm)
 No. 3

SEC. 34 T. 13 R. 20W
 NE SW NE

Total Depth. 3835'
 Comm. 9-5-56 Comp. 9-15-56
 Shot or Treated.
 Contractor.
 Issued. 12-1-56

County Ellis
 KANSAS



CASING:
 8 5/8" 269'
 5 1/2" 3830'

Elevation. 2241' DF

Production. 81 B OPD

All Meas. fr RB Figures Indicate Bottom of Formations.

surface soil	100
shale	270
shale-sand	900
shale	1030
sand	1275
red bed	1539
Anhydrite	1580
shale-shells	2015
lime-shale	3835
Total Depth	

TOPS:

Anhydrite	1539
Topeka	3211
Heebner	3465
Toronto	3486
Lansing	3504
B/Kansas City	3757
Marmaton	3768
Arbuckle	3827

DST #1 - 3532-40 Open 1 hr.
 light blow & gas to surf. 55
 min. Rec. 1730' fluid, 60'
 very slightly OCGM. 60' slight-
 ly OCM, 60' oily mud, 240' muddy
 oil, 550' clean oil, 760' salt
 wtr.

DST #2 - 3659-3671 light blow for
 12 min. & rec. 50' mud, 1200# BHP