

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas


Company - J. M. HUBER CORP.
Farm - Engel No. 1

SEC. 36 T. 13 R. 20W
NW NW NW

Total Depth. 3899
Comm. 6-21-49 Comp. 7-6-49
Shot or Treated.
Contractor. J. M. Huber Corp.
Issued. 8-20-49

County. Ellis

KANSAS



CASING:
10" 195'

Elevation. 2186 ind

Production. Dry and aband.

Figures Indicate Bottom of Formations.

sub soil	10
post rock	30
shale, shells	650
sand, shells	735
shale	775
sand strks, shale,	
shells	910
shale, shells	940
sand	1260
shale, shells	1320
redbed, shale, shells	1485
lime	1540
shale, shells	1580
shale, shells, lime Strk.	
	1855
shale, shells	2115
lime	2130
lime, shale	2570
sand brkn, lime, shale	2705
lime, shale	2900
lime, shells, shale	3015
shale, shells	3090
lime	3130
lime brkn, shale	3245
lime, shale	3520
lime	3525
lime, shale	3670
lime	3720
lime, shale	3766
lime cherty	3795
sand	3827
sand, lime	3840
lime cherty	3871
lime cherty, shale	3899
Total Depth	

DST, 3396-3415, open 15 mins.
rec. 900' salt water. BHP 1025#.
DST 3514-25, open 50 mins.
rec. 185' salt water. BHP 1025#.
DST 3532-70, open 50", rec. 570'
salt water. BHP 1040#.
DST 3662-74, open 40 mins. rec.
1450' salt water.
DST 3819-27, open 50 mins., rec. 20'
mud.
DST 3827-40, open 50 mins. rec. 10'
mud.
DST 3842-99, open 1 hr, rec. 2430'
salt water. Dry and aband.

Tops: Sample	
Topeka	3194
Heebner	3441
Top Lansing	3482
Base K. C.	3739
Conglomerate	3805
Arbuckle	3824

3482
3194
1288
1290