

COMPLETION REPORT

Egger # 1  
NE NE SW of 6-13S-20W  
Ellis County, Kansas

3-19-65      We moved in Cable Tools and swabbed hole down to top plug.  
(have not drilled plug or shoe)   Rotary mud coming in casing,  
pumped flag down and we have a hole or bad thread at 3064 feet.

3-20-65      Squeezed hole (Halliburton), shut down for cement to set.

3-22-65      Swabbed hole down - did not get squeeze. Resqueezing today  
(Halliburton) and we shut down for cement to set.

COMPLETION REPORT  
(Cont'd)

Egger # 1  
NE NE SW of 6-13S-20W  
Ellis County, Kansas

3-27-65      Well swabbing 3 barrels oil per hour, natural no water.

3-28-65      12 hour fillup, 1100 feet oil, ran tubing, acidized with 250 gallon mud acid (MCA) (Halliburton) maximum pressure 1200#, fed at 600#, on vacuum 2 minutes. Pulled tubing, swabbed load, swabbed 12 barrels oil per hour for 2 hours, (no water)

3-29-65      10 hour fillup, 2080 feet oil (no water) baling hole clean. We will perforate and squeeze Dakota section and put well on pump.