


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO. & H. W. PATTON
Farm- Cromb No. 4

SEC. 1 T. 13 R. 21W
NE NW SE

Total Depth. 3906'
Comm. 12-13-61 Comp. 12-28-61
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 6-30-62

County Trego
KANSAS



Elevation. 2171' KB

Production. SWDW

CASING:

10 3/4" 200' cem w/150 sx.
7" 3885'

Figures Indicate Bottom of Formations.

shale	375
sand & shale	625
shale	700
shale-sand	1210
red bed & shale	1515
Anhydrite	1550
shale - shells	1820
shale - lime shells	2127
lime & shale	2610
shale - lime	3018
lime & shale	3244
lime	3763
lime-chert-shale	3790
lime	3808
shale-lime-sand	3839
Arbuckle	3856
dolomite - sand	3906
Total Depth	

TOPS: ELECTRIC LOG

Anhydrite	1520
Topeka	3188
Heebner	3416
Toronto	3435
Lansing	3452
Base Kansas City	3704
Marmaton	3762
Conglomerate	3799
Erosional Arbuckle	3816
Arbuckle	3838
Reagan	3881
Pre-Cambrian	3902

DST #1 3799-3831', op 1 hr., very weak
blow for 17 min. Rec. 20' slightly oil
specked mud & 32' mud. IBHP 710#/20 min.,
FBHP 165#/20 min., IFP 105#, FFP 145#.

DST #2 3841-3853', op 1 hr., good steady
blow thruout. Rec. 240' muddy water &
few oil specks. BHP 1105#/20 min., IFP 0#,
FFP 130#.