

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING -H. W. PATTON
Farm- Cromb No. 6

SEC. 1 T. 13 R. 21W
SE NW NE

Total Depth. 3835'

Comm. 8-12-63


Comp. 8-22-63

Shot or Treated.

Contractor. Murfin Drlg.

Issued. 4-25-64

County Trego
KANSAS



CASING:

Elevation. 2181' KB

8 5/8" 195' cem w/150 sx
5 1/2" 3830' cem w/ 100 sx

Production. 5 1/2 BO / 32 BWPD

Figures Indicate Bottom of Formations.

sand & surface clay	55
shale	505
sand & shale	850
shale w/sand streaks	1005
sand	1235
red bed	1512
anhydrite	1561
shale -shells	1815
shale & shells-salt	2159
shale-lime	2492
lime-shale	2930
shale-lime	3194
lime	3720
lime-shale-chert	3785
lime-chert	382-
Arbuckle	3835 RTD
Total Depth	

TOPS: SMP	
Anhydrite	1516
Topeka	3194
Heebner	3423
Toronto	3443
Lansing	3460
Base Kansas City	3707
Marmaton	3757
Arbuckle	3815