


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND OIL & GAS CO.  
Farm - A. I. Cromb No. 2.

SEC. 1 T. 13 R. 21 W  
CW  $\frac{1}{2}$  NW NE  
1 980' NSL 330' E WL NE  $\frac{1}{4}$

Total Depth. 3850'  
Comm. 12-3-43 Comp. 1-8-44  
Shot or Treated.  
Contractor.  
Issued. 3-18-44 Rotary 9-3823  
Cable 3823-50

County. Trego  
KANSAS



Elevation. \_\_\_\_\_

Production. Swb Temp. Pot. 13 B.  
6 hrs

CASING:  
13" 108'4" Cem.  
8 5/8" 1200'4" Cem.  
5 1/2" 3837'9" Cem.

Figures Indicate Bottom of Formations.

cellar (surface rock)	0-9	Tops:	
surface clay	40	Anhydrite	1524
shale & lime	117	Topeka, no shows	3191
shale & shells	570	Iansing, no shows	3455
shale & iron	665	Base K.C. Lime	3701
shale & shells	890	Marmaton Chert	3751
shale w/strks sand	950	Cherty Congl.	3797
sand	970	Arbuckle Dolo.	3823-50
sand & shells	1175		
red beds	1524		
anhydrite	1568		
shale & shells	1660		
shale	1705		
shale & shells	1800		
shale & lime	1877		
shale	1890		
shale & salt	2105		
shale & lime	2200		
lime brkn	2300		
shale & lime	2435		
brkn lime	2500		
lime	2568		
lime hd	2630		
shale & shells	2668		
lime brkn	2752		
lime	2790		
shale	2820		
lime	3005		
shale	3098		
lime	3131*		
*Twisted off drill pipe, caught fish & stuck drill pipe, spotted oil & rec. drill pipe & fish(108 hrs)			
shale	3131-3193		
lime	3270		
lime brkn	3293		
lime	3544		
lime & shale	3592		
lime cherty	3604		
lime	3751		
chert	3797		
cherty conglomerate	3805		
shale maroon, gy & green sdy w/various colored pieces of chert	3815- 3827 $\frac{1}{2}$		
lime	3829		
dolomite	3832		
dolomite porous	3836 $\frac{1}{2}$		
dolomite dense	3850		
Total Depth.			