

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company *Murphy* STANOLIND OIL & GAS CO.
Farm A. I. Cromb No. *5*


owner
SEC. 1 T. 13 R. 21W
SE SW NE
330' N of SL, 990' E of WL

Total Depth. 3880
Comm. 5-9-55
Shot or Treated.
Contractor.
Issued. 8-6-55

Comp. 5-24-55
1961

County Trego

KANSAS



8 5/8 @ CASING: 208' w/ 150 sx cmt.

Elevation. 2172 GL

Production. Dry

Figures indicate Bottom of Formations

surface clay	20
sand	75
shale & shells	320
shale	400
shale & shells	800
sand & shells	1200
shale	1350
shale & shells	1518
anhydrite	1555
shale & shells	1630
shale & lime	3220
lime	3705
lime & shale	3755
lime & chert	3804
lime & shale	3825
lime	3874
granite	3880
Total Depth	

SCOUT TOPS:

Anhydrite	1518
Heebner	3415
Kansas City	3452
Eros. Arbuckle	3801
Solid Arbuckle	3814
Reagan	3852
Pre-Cambrian	3872

DST #1: 3660-73, open 1 hr., SI 20 min., rec. 3' SLOCM, IFP 0#, BHP 855#.

DST #2: 3792-3804, packer failed, no test.

☐ #3: 3793-3804, open 1 hr., SI 20 min., rec. 3' mud, NS, IFP 0#, FFP 0#, BHP 0#

DST #4: 3818-25, open 1 hr., SI 20 min., rec. 2' OCM, 1' oil, IFP 0#. ☐ 0#, BHP 35#

DST #5: 3825-80, open 1 hr., SI 20 min., rec. 250' mud, 2100' HOCSW, IFP 140#, FFP 1130#, BHP 1130#

DST #6: 3814-22, open 1 hr., SI 20 min., IFP 0#, FFP 0#, BHP 390#

Core #1 3799-3804 rec. 3' 8"