


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.
Farm - Spilker "B" No. 1.

SEC. 1 T. 13 R. 21 W
CWL NE NW

Total Depth. 3928' PB 3282'
Comm. 1-6-44 Comp. 2-10-44
Shot or Treated.
Contractor.
Issued. 3-4-44 Rotary O-3927
Cable 3927-28

County. Trego
KANSAS



CASING:
8 5/8" 127' Cem.
5 1/2" 3927' Cem.

Elevation. _____

Production. Temp. Abnd.

Figures Indicate Bottom of Formations.

surface	0-50	Drd cement @ 3910
clay & shale	127	Ran lane-Wells Gamma Ray Log
cement & shale	140	Perf. 12 shots 3897-3904
shale & shells	894	Hole loaded w/fresh wtr before perforating
sand	914	
shale & shells	1076	Started swbg 11:20 P.M.
red bed & shale	1252	2-6-44
shale	1272	Pulled swab 4 times & swbd
shale & shells	1541	down to 1500' from top
anhydrite	1585	Unable to lower fluid below
shale & shells	1945	that depth.
salt	2085	Pulled swab 10 times-shut
shale & shells	2135	down; while swbg pulled 400'
lime sdy	2192	to pull
sand & shale	2250	Set lane-Wells Plug @ 3895 &
shale & sdy lime	2310	dried up hole
lime gy sdy	2374	Perf. 11 shots 3855-58--150'
lime sdy	2512	wtr per hr-no sh oil
lime	2535	Started to bail - 1BWPH, no
lime sdy	2624	show of oil
lime brkn	2655	Bailed every hr for 8 hrs
shale	2684	Bailer on well equaled 1/2 Bbl
lime sdy	2720	Perf. 12 shots 3224-30 in
lime	2840	Topeka -- had 190' fluid,
shale sdy	2908	total -- no sh of oil
lime brkn	2970	Ran bailer at 12:00 noon
lime	3020	2-8-44--had 190' fluid
lime sdy	3075	Ran bailer at 1:00 P.M.
lime	3150	2-8-44--had 190' fluid
lime & shale	3206	6 shots 3220-24
lime	3465	6 shots 3230-34
lime cherty	3476	Ran bailer in 30-minutes &
lime	3732	had 35' increase in fluid--
lime cherty	3782	no show
chert & lime	3798	Plugged back to 3282 w/wooden
lime cherty hd	3818	plug, crushed rock & 2 sx
lime cherty		Cal-Seal.
(conglomerate)	3842	Acidized w/500-gal.
coring	3881	Temporarily abnd.
lime	3886	
sand	3896	
sand cherty	3920	
chert (conglomerate)	3928	
Total Depth.	P.B. 3282	

Formation Tops - DF:
Iansing 3461
Base Kansas City 3719
Marmaton Chert 3762
Conglomerate 3822
Arbuckle 3842
Reagan 3897
Pre-Cambrian 3920