

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ALVA OIL
Farm- Egger

No. 1

SEC. 11 T. 13 R. 21W
NW NE NE

Total Depth. 3843'

Comm. 9-17-60

Comp. 9-27-60


Shot or Treated.

Contractor. John O. Farmer, Inc.

Issued. 11-12-60

County Trego

KANSAS



CASING:
8 5/8" 160' cem w/115 sx.

Elevation. 2153' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale	875
shale & sand	1015
sand	1230
shale & red bed	1495
redbed & shale	1520
Anhydrite	1560
shale & shales	1815
shale & lime	2480
lime & shale	2550
shale & lime	3210
lime & shale	3760
lime, shale, chert	3780
cherty lime	3800
lime, shale, chert	3804
shale, lime	3822
Arbuckle	3843
Total Depth	

TOPS:	
Anhydrite	1513
Topeka	3149
Heebner	3396
Toronto	3419
Lansing	3432
Base Kansas City	3681
Marmaton	3741
Conglomerate	3785
Arbuckle	3816

DST 3751-3773', shut in 20 mins., op 1 hr.,
shut in 20 mins., weak blow for 35 mins.,
intermittent for remainder. Rec. 45' slightly
oil cut watery mud. IBHP 1205#, IFP 18#,
FFP 50#, FBHP 1110#.