


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRLG.
Farm- Egger No. 2

SEC. 12 T. 13 R. 21W
SE SW

Total Depth. 3824'
Comm. 11-25-58 Comp. 12-5-58
Shot or Treated.
Contractor.
Issued. 1-24-59

County Trego
KANSAS



Elevation. 2151' DF

Production. 182 BOPD

CASING:

8 5/8" 188' cem w/140 sx.
5 1/2" 3817.5' cem w/200 sx.

Figures Indicate Bottom of Formations.

clay	20
sand	40
shale	187
shale & shells	345
sand	1260
red bed & shale	1380
red bed	1507
Anhydrite	1554
shale & shells	2095
lime & shale	3170
lime	3746
chert & lime	3756
lime	3788
Conglomerate	3816
Arbuckle	3819 RTD
Arbuckle	3824 CTTD
Total Depth	

TOPS:

Anhydrite	1507
Heebner	3406
Toronto	3426
Lansing	3444
Maxmaton	3748
Conglomerate	3785
Arbuckle	3814

DRILL STEM TESTS:

#1 3201-18, op 21", rec. 12' mud, EHP 830#.

#2 3472-87, op 45", gas 17", flowed oil
in 38" BHP 1290#.

#3 3526-36, op 30", rec. 2040' gas, 295'
oil & 60' water. EHP 1320#.

#4 3568-87, op 1½ hrs. rec. 150' oil
cut mud. EHP 350#.

#5 3641-52', op 30" weak blow 15". Rec.
20' mud to oil, BHP 100#.

Acidized w/500 gal.