


640 Acres
N



Locate well correctly

17-12-21W

Lease Name: Petty "C" Well No. 3
 Well Located: NW NE SW
SEC 19 TWP 13S RGE 21W
 Operator: Pickrell Drilling Company
 Address: 705 Fourth National Bank Bldg., Wichita, Ks.
 Elevation: Ground D.F. K.B. 2261
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 11/9 19 73 Drilling Completed: 11/19 19 73
 Well Completed: 11/19 19 73 Total Depth 4061 RTD
 Initial Production: N/A

Casing Record

Size: 8 5/8" Set at 223' Size: Set at
 Size: Set at Size: Set at

Liner Record

Size: Set from To

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8 5/8"</u>	<u>140sx</u>	<u>Common</u>
<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>

Electric Log Run (Show type log and depths covered)

Great Guns Gamma-Ray Neutron Guard Caliper Electric Log

(Fill in formation and related information on reverse side)

19-13-21w

FORMATION, TESTING AND COMPLETION RECORD

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom	
Top Soil	0	30	DST #1, 3593-3615, open 2 hours, weak to good blow.
Post Rock	30	65	Recovered 30' gas in pipe & 300' heavily mud cut oil.
Shale	65	837	ISIP 449#/30", FSIP 461#/60", FP 46-138#.
Shale & Shells	837	1175	
Sand	1175	1395	DST #2, 3622-3647, open 2 hours, very weak steady blow
Shale & Red Beds	1395	1630	Recovered 120' heavily oil cut mud. ISIP 219#/30",
Shale & Shells	1630	1683	FSIP 242#/60", FP 46-92#.
Anhydrite	1683	1722	
Shale & Shells	1722	1945	DST #3, 3645-79, open 1 hour, very weak 8" blow.
Shale	1945	2360	Recovered 5' oil-specked mud. ISIP 81#/30", FSIP
Shale & Lime Stringers	2360	2565	69#/30", FP 46-58#.
Lime Shale,			
Chalk & Sand	2565	2925	DST #4, 3750-98, open 2 hours, weak steady blow. Recov
Lime & Shale	2925	3347	ered 65' heavily oil cut mud. ISIP 173#/30", FSIP
Shale & Lime	3347	3480	629#/30", FP 58-92#.
Lime & Shale	3480	3615	
Lansing Lime & Chert	3615	3647	DST #5, 4038-4056, open 1 hour weak 12" blow.
Lime	3647	3679	Recovered 10' slightly oil cut mud. ISIP 58#/30",
Lime & Shale & Sand	3679	3734	FSIP 46#/30", FP 35-46#.
Lime	3734	3811	
Lime & Shale	3811	3950	
Lime	3950	3976	
Lime & Chert, RTD	3976	4061	

