



Home Office: Great Bend, Kansas
P. O. Box 393 GLadstone 3-7903

COMPANY Hinkle Oil Company WELL Leiker #1
DATE 10-29-58 COUNTY Ellis STATE Kansas
TEST NO. #3 TICKET NO. 7580-K TYPE TEST open hole (conventional)
TEST APPROVED BY James Rahtin WESTERN REPRESENTATIVE Roy Bruce

TEST DATA:

Tested From 3434' To 3442' Depth 3442'
Hydrostatic Mud Pressure—Initial (A) 1950# Final (B) 1950#
Flow Pressure—Initial (B) Cushion 440# Final (C) 300#
Bottom Hole Pressure—Initial (F) - - Final (D) 700#
Tool Open 1 Hr. Min.; Shut-in-Initial - - Hr. Min.; Shut-in-Final - -
Chokes; Surface 1/2" Bottom 3/4" Fluid Cushion: Type - - Amount - - - -
Recovery: 260' Oil cut mud.

SURFACE DATA:

BLOW: Light steady blow thru out test.

Maximum Surface Pressure - - - - Did Well Flow? No

Description of Flow	Time	Max. Pressure	Size Surface Choke
<u>- - - -</u>	<u>- - - -</u>	<u>- - - -</u>	<u>- - - -</u>
<u>- - - -</u>	<u>- - - -</u>	<u>- - - -</u>	<u>- - - -</u>
<u>- - - -</u>	<u>- - - -</u>	<u>- - - -</u>	<u>- - - -</u>


GENERAL OPERATIONAL DATA:

Hole Size: Main Hole 7 7/8" Rat Hole - - - - Drill Pipe Size 4 1/2" F.H.
Hole Condition Poor Mud Weight 10. Viscosity 40
Type Pressure Recorder Western Recorder No. 39 & 40 Date Calib. 7-1958
Extra Equipment: Dual Packer Yes Jars No Safety Joint No
Was Test Recovery Reversed Out? No Bottom Hole Temperature Not taken
Number of Copies Requested Five

REMARKS: Bridge 30' off bottom, slid tool to bottom.

Hinkle Oil Co.
Leiker #1

Test # 3
TKT. #7580-K



This is an actual photograph of recorder chart.

PRESSURE DATA

Point

Pressure

(A) Initial Hydrostatic Mud	1950#
(B) Initial Flow	Cushion 440#
(C) Final Flow	300#
(D) Final Shut-In	700#
(E) Final Hydrostatic Mud	1950#
(F) Initial Shut-In	
