

WEBER

LEASE

6

WELL NO.

1

TEST NO.

GULF OIL CORPORATION

COMPANY

KANSAS

DISTRICT



OIL WELL CEMENTING COMPANY

Date 1-18-54

Ticket No. 64041

HOWCO District Hays, Kansas

Kind of Job Open Hole

Price \$215.00

Second Packer Assembly -

Safety Joint -

Extra Folder Charge -

Jars -

Total \$215.00

Witnessed By Simington

Tester Cullum

HOLE & TOOL DATA

Total Depth	Casing Perforations	
	Top	Bottom
3336'	-	-
Top Packer Depth 3325'	Bottom Packer Depth -	-
Casing or Hole Size 9"	Liner or Rathole Size -	-

Formation Tested Kansas City

Size Drill Pipe 4 1/2" API FH Size Drill Collars -

Size Bottom Choke 1" Size Surface Choke 1 1/2"

Size Tool Valve 1" Size Pilot Valve -

Size Hook Wall Packer - Size Rings - No. Rings -

Size D. E. Wall Packer 8" No. Packers 1

PRD Device No. 1734 Blanked Off Yes

Size & Length Anchor 4 1/2" x 11'

REMARKS: Tool opened with a weak blow throughout the test.

Recovered 65' muddy salt water.

Tool Open 1 Hour

Final Flow Pres. 41 p.s.i.

Time Closed In 15 Minutes

Closed In Pres. 893 p.s.i.

Final Hydro Mud Pressure 1797 p.s.i.

Amount of Cushion None

All depths measured from Kelly Bushing

No. Folders Reproduced

5

PRESSURE

TIME

64041

Each Horizontal Line Equal to 1000 p.s.i.

