

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- MAGNOLIA PETROLEUM CO.
Farm J. P. Losey No. 1

SEC. 24 T. 13 R. 30W
SE SW SW

Total Depth. 4569
Comm. 4-15-55 Comp. 5-3-55
Shot or Treated.
Contractor. Barnett Drilling Co.
Issued. 7-16-55

County Gove

KANSAS



Elevation. 2865 DF

Production. Dry

CASING:
9 5/8 @ 197' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

surface hole	198
shale & shells	1550
sandy shale	1675
shale	1705
sand	1755
shale	2170
shale & shells	2275
anhydrite	2310
shale & shells	2595
shale	2800
lime & shale	2965
lime	4569
Total Depth	

TOPS:

Heebner	3879
Lansing-KC	3916
Ft. Scott	4392
Mississippian	4480

DST #1: 3955-80, open 1 hr., SI 20 min. good blow, rec. 180' drlg. mud, 180' water, BHP 930#

DST #2: 4099-4135, open 1 hr., SI 20 min. weak blow 6 min. rec. 25' muddy water, 1' free oil, FP 0#, BHP 180#

DST #3: 4149-65, open 1 hr., SI 20 min. weak blow 13 min. rec. 13' SOCM, FP 0#, BHP 80#

DST #4: 4332-57, open 1 hr., SI 30 min. good blow, rec. 50' O&GCM, 190' gas in pipe, FP 30#, BHP 940#

DST #5: 4386-4415, open 1 hr. SI 20 min. rec. 10' mud, BHP 25#

DST #6: 4495-4569, open 1 hr., SI 20 min. weak blow, rec. 20' drlg. mud w/ specks dead oil, BHP 905#