


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.  
Farm- Sexson "A" No. 1

SEC. 29 T. 13 R. 42W  
SE SE NW  
~~330' fr EL, 330' fr SL~~  
2310 FNL! 2976 FEL-1000

Total Depth. 5240'  
Comm. 6-22-58 Comp. 7-13-58  
Shot or Treated.  
Contractor. Chas. Hulme Drig. Co.  
Issued. 8-23-58

County Wallace  
KANSAS



CASING:  
10 3/8" 516' cem w/550 sx.

Elevation. 3878' DF

Production. Dry

Figures indicate Bottom of Formations.

surface soil, sand,	
and shale	200
sand & blue clay	517
shale & sand	585
blue clay	975
shale	1490
shale & shells	1790
shale & lime	1975
shale & shells	2105
shale & lime	2305
shale & red bed	2450
shale & lime	2518
Anhydrite	2540
shale & lime	2585
shale & shells	2870
shale & lime	2950
lime	3065
lime & shale	3195
lime	3395
lime & shale	3455
lime	4695
sandy lime	4742
lime	4825
lime & shale	4870
lime	4956
sandy lime	4992
lime & shale	5023
lime	5051
sand & lime	5058
shale	5130
lime	5170
lime & shale	5194
lime	5240
Total Depth	

TOPS:	
Topeka Lime	3986
Heebner Shale	4198
Toronto	4230
Lansing Lime	4252
Base Kansas City	4602
Marmaton Lime	4634
Cherokee Lime	4782
Morrow Shale	5041
Morrow Sand	5048
Morrow Lime	5118
St. Louis	5194

Ran Schlumberger Survey.

DST #1 packer set at 5039', used 19' anchor  
op 1 hr, good blow thruout, rec. 1290'  
of slightly gas cut water, IBHP 1030# in  
20 mins, IFP 80#, FFP 56#, FBHP 1000# in  
20 mins.

DST #2 packer set at 5145', used 95' anchor,  
op 1 hr, good blow for 1 hr, rec. 1130'  
of muddy salt water, IBHP 1900# in 20 mins.  
IFP 50#, FFP 450#, FBHP 870#. 20 mins.