

16-14-10W

WELL COMMENCED: October 30, 1972
DATE COMPLETED: November 7, 1972

L. G. Stephenson -
International Resources Corp
BAKER "A"-#5
SE/4 SW/4 SE/4
Section 16-T14S-10W
Ellsworth County, Kansas

ELEVATION 1741 K.B.

0 - 72' Clay
72 - 450' Shale & Sand Streaks
450 - 565' Shale & Red Bed
565 - 596' Anhydrite
596 - 780' Red Bed
780 - 1380' Shale & Lime
1380 - 2448' Lime & Shale
2448 - 2738' Lime
2738 - 2743' Shale
2743 - 2758' Lime & Shale
2758 - 2772' Lime
2772 - 2833' Shale
2833 - 2852' Br. Lime
2 - 3005' Lime
3005' RTD

FORMATION DATA

ANHYDRITE	565
BROWNVILLE	2079
GRANDHAVEN	2122
DOVER	2143
TARKIO	2200
ELMONT	2266
BURLINGAME	2342
HOWARD	2419
TOPEKA	2448
HEEBNER	2738
TORONTO	2758
DOUGLAS	2772
BR. LIME	2833
KANSAS CITY	2852
RTD	3005

SURFACE PIPE: Set used
8-5/8", 28# at 267' with
160 sacks Sunset cement.

PRODUCTION PIPE: Set used
5 1/2" casing, 14 1/2# at 2998'
with 250 sacks 50/50 Pozmix
with 10 bbls. salt flush
ahead of cement.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Leonard Williamson of lawful age does swear and state that the
facts and statements herein contained are true and correct to the best of
his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 8th day of November 1972.

My Comm. Expires:
April 11, 1974

Donald M. Hague
Notary Public

