

16-14-10W

DATE COMMENCED: October 15, 1973
DATE COMPLETED: October 21, 1973

L. G. Stephenson
K. VOPAT #6
Approx. NE SE SE
Sec. 16-14-10W
Ellsworth County

ELEVATION: 1726 K.B.

0	-	74'	Clay & Post Rock
74	-	89'	Sand
89	-	260'	Blue Shale
260	-	533'	Shale, Sand & Red Bed
533	-	563'	Anhydrite
563	-	874'	Red Bed
874	-	1195'	Shale
1195	-	1625'	Shale & Lime
1625	-	2429'	Lime & Shale
2429	-	2718'	Lime
2718	-	2722'	Shale
2722	-	2738'	Shale & Lime
2738	-	2752'	Lime
2752	-	2805'	Shale
2805	-	2826'	Br. Lime
2826	-	2970'	Lime
		2970'	RTD

FORMATION DATA

ANHYDRITE	533
BROWNVILLE	2063
GRANDHAVEN	2106
DOVER	2128
TARKIO	2184
ELMONT	2246
BURLINGAME	2324
HOWARD	2392
SEVERY SAND	2416
TOPEKA	2429
HEEBNER	2718
TORONTO	2738
DOUGLAS	2752
BROWN LIME	2805
KANSAS CITY	2826
RTD	2970


SURFACE PIPE: Set used
28# 8-5/8" surface pipe at
260' with 165 sacks cement.

PRODUCTION CASING: Set
used 5 1/2" casing, 14# at
2969' with 75 sacks 60/40
pozmix, 12% salt sat.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age does swear and state that the
facts and statements herein contained are true and correct to the
best of his knowledge.



Larry Curtis

Subscribed and sworn to before me this 23 day of October 1973.

My Comm. Expires:
April 11, 1974

Martha M. Hagure
Notary Public