

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Cock "B" No. 1

SEC. 19 T. 14 R. 10W
NEc SW
330' S & 490' W of Center

Total Depth. 3178' P.B.T.D. 3036'
Comm. 10-2-46 Comp. 10-17-46
Shot or Treated. 1000 gals. 11-2-46 & 2799-2810
Contractor. Corbett-Barbour Drilling Co.
Issued. 1-4-47

County. Ellsworth
KANSAS



Elevation. _____

Production. Dry.

CASING:

2-5/8" 475' Com
5-1/2" 3075' Com

Figures Indicate Bottom of Formations.

soil	0-20
sand	45
clay	60
clay & shells	145
sand	160
shale & shells	300
sand hrd	350
shale & shells	455
anhydrite	485
red bed	665
shale & shells	825
shale, shells & salt	1045
shells & salt	1095
lime & shale	1195
anhydrite & lime	1305
shale & lime	1430
lime	1500
sdv lime	1520
lime	1740
lime & shale	2035
shale	2180
shale & lime	2425
shale	2435
lime	2485
lime & shale	2565
lime	2765
shale	2790
lime	3178
Total Depth	

Tops:

Lansing	2775
Arbuckle	3139
Penetration	39

C. O. to top of plug at 3036 SIM.

Perf. 12 shots 2988-99
Perf. 12 shots 2855-66
3-1/4 bailers wtr in 2 hrs.
Set Lane-Wells plug at 2840'.
Perf. 12 shots 2799-2810
Perf. 24 shots 2800-08
Rainbow show oil