

DRILLERS' WELL LOG

15-14-10W

DATE COMMENCED: September 19, 1973
DATE COMPLETED: September 28, 1973

L. G. Stephenson
PTACEK #1
SW/4 SW/4 NE/4
Section 15-T14s-R10W
Ellsworth County, Kansas

ELEVATION: 1783 K.B.

0	-	45'	Clay & Post Rock
45	-	266'	Blue Shale
266	-	580'	Shale & Sand
580	-	604'	Anhydrite
604	-	945'	Red Bed
945	-	1250'	Shale
1250	-	1880'	Shale & Lime
1880	-	2160'	Shale
2160	-	2525'	Lime & Shale
2525	-	2773'	Lime
2773	-	2776'	Shale
2776	-	2867'	Lime & Shale
2867	-	3091'	Lime
		3091'	RTD

FORMATION DATA

ANHYDRITE	580
GRANDHAVEN	2155
DOVER	2177
TARKIO LIME	2233
ELMONT	2300
HEEBNER	2773
TORONTO	2793
DOUGLAS	2807
BR. LIME	2867
KANSAS CITY	2885
RTD	3091

SURFACE PIPE: Set used
805/8" pipe, 28# at 266'
with 165 sacks Sunset
cement.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Larry Curtis, of lawful age does swear and state that
the facts and statements herein contained are true and correct to the
best of his knowledge.

Subscribed and sworn to before me this 1st day of October 1973.

My Comm. Expires:
April 11, 1974

Larry Curtis
Notary Public

