

16-14-10W

DATE COMMENCED: October 12, 1972
 DATE COMPLETED: October 20, 1972

L. G. Stephenson
 BAKER A-4
 Approx. 40' W & 61" N of
 SW NW SE
 Sec. 16-14s-10w
 Ellsworth County

ELEVATION: 1733 K.B.

0	-	68'	Clay
68	-	100'	Sand
100	-	295'	Shale & Sand Streaks
295	-	420'	Sand & Shale Streaks
420	-	534'	Red Bed
534	-	558'	Anhydrite
558	-	850'	Red Bed
850	-	1185'	Shale & Shells
1185	-	2426'	Lime & Shale
2426	-	2718'	Lime
2718	-	2722'	Shale
2722	-	2738'	Lime & Shale
2738	-	2751'	Lime
2751	-	2816'	Shale
2816	-	2834'	Lime & Shale
2834	-	3107'	Lime
3107	-	3125'	Lime & Shale
		3125'	RTD

FORMATION DATA

Anhydrite	534
Tarkio	2176
Elmont	2244
Burlingame	2319
Howard	2388
Topeka	2426
Heebner	2718
Toronto	2738
Douglas	2751
Br. Lime	2816
Kansas City	2834
Base K.C.	3107
RTD	3125

SURFACE PIPE: Set 261' of 8-5/8", 28#, surface pipe with 165 sacks Sun-set cement.

PRODUCTION CASING: Set used 5 1/2", 14 1/2# casing at 3117' with 225 sacks of 60/40 pozmix, salt sat., 10 bbls. salt flush ahead of cement.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 25 day of October 1972.

My Comm. Expires:
April 11, 1974

Norathy M. Hague
 Notary Public

