

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WILL P. ASH

SEC. 19 T. 14 R. 10W
 LOC. SE SE NE

FARM Adamek

NO. 1

COUNTY Ellsworth

TOTAL DEPTH 3210'


COMM. 2-27-67

COMP. 3-5-67

SHOT OR TREATED

CONTRACTOR Sage DRlg

ISSUED 8-19-67



CASING

20	10	
15	8	5/8" 261' cem w/ 150 sx
12	6	
13	5	

ELEVATION 1684' KB

PRODUCTION Temp Abdn/ Arb

Surface Soil & Sand	0	263
Hard Sand	263	322
Hard Sand & Pyrite	322	361
Red Bed	361	448
Anhydrite	448	479
Shale & Shells	479	1035
Shale & Lime	1035	1990
Lime, Shale & Sand	1990	2290
Shale & Lime	2290	2555
Lime & Shale	2555	2818
Lime	2818	2837
Lime & Shale	2837	2924
Lime	2924	2997
Lime & Shale	2997	3178
Shale & Chert	3178	3204
Lime	3204	3210

MAR 10 1967

TOPS: SCOUT	
Indian Cave	2013
Grand Haven	2065
Dover	2088
Tarkio Lansing	2142
Will Shale	2162
Howard	2353
Topeka	2429
Heebner	2680
Brown Lime	2774
Lansing	2793
B/ Kansas City (s)	3065
Arbuckle (smp)	3204

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
 Wayne W. Kahmeyer

Subscribed and sworn to before me this 7th day of March, 1967.

[Handwritten Signature]