

21-14-10W
C E/2 NE SW

COMPANY: JUN 20 1970

CONTRACTOR:

FARM:

LOCATION:

COMMENCED:

COMPLETED:

elev. 1686' KB

Glen N. Rupe
American Drilling Corporation
Vopat A-3

Section 21-14S-10W, Ellsworth
County, C E/2 NE SW

5-1-70 120 BOPD/NW
2 KC
5-6-70


0	to	248
248	to	315
315	to	460
460	to	497
497	to	523
523	to	1280
1280	to	2452
2452	to	2695
2695	to	2815
2815	to	2847
2847	to	2895
		2895

Clay & Sand
Shale
Sand
Red Bed
Anhydrite
Shale & Shells
Lime & Shale
Lime
Lime & Shale
Core
Lime
Total Depth

*anhydrite 49
2 KC 2802*

Set 249' feet of 8-5/8" surface pipe w/ 175 sacks of Sunset Cement

Set 2887' of 4-1/2" Casing w/ 150 sacks of 60/40 Posmix.



CERTIFICATE

I, Larry G. Stephenson, do hereby certify that the above and foregoing is a true and correct copy of the drillers log of the #A-3 Vopat, Section 21-14S-10W, Ellsworth County, Kansas as reflected by files of the American Drilling Corporation.

Larry G. Stephenson

Larry G. Stephenson